

ADDENDUM NO. 2

UA RESEARCH AND TECHNOLOGY PARK
PEDESTRIAN IMPROVEMENTS
Facilities Management Division
University of Arkansas
Fayetteville, Arkansas
Plans No. 018-0073
October 26, 2018

The Specifications and Contract Documents for the above project are hereby changed or clarified in the following particulars:

GENERAL CLARIFICATION

- 1) The following questions were submitted by Plan Holders. The answers are as follows:
 - A. Question: Is 6x6-W1.4xW1.4 WWF per the UA Facilities Management Landscape Standards Drawing required for the 4" Concrete Trail??
Answer: Yes, add 6x6-W1.4xW1.4 WWF centered in the slab on Detail #5 on Sheet C3.
 - B. Question: Are the #4x18" dowel bars smooth or deformed #4 rebar on Sheet C3, Detail 5?
Answer: All dowel bars are to be smooth dowel bars.
 - C. Question: Are the sleeves for the #4 dowel bars mentioned above to be speed dowels or plain sleeves?
Answer: Plain Sleeves
 - D. Question: Are the #3 x18" dowels smooth or deformed per detail 4A/Sheet C3?
Answer: All dowel bars are to be smooth dowel bars.
 - E. Question: Will silt fence be required along the entire sidewalk?
Answer: Refer to the Stormwater Pollution Prevention Plan (SWPPP) included in the Bid Documents for sediment control plans.
 - F. Question: Specifications Section 32 17 23, Part 2 – PRODUCTS 2.1, A., B., & C; This spec only mentions Paint for pavement markings and does not mention thermoplastic marking at all. Sheet C3 of plans, Detail 6 states markings to be thermoplastic. Please Clarify
Answer: Thermoplastic markings will be required. Provide Thermoplastic Pavement Markings as per Arkansas 2014 Standard Specification for Highway Construction, Section 791.
 - G. Question: Sheet C3, Detail 6; Is the full length of trail to have thermoplastic center line or is center line to only be install in offsets?
Answer: Centerline Marking is only required at offsets as shown in the detail.

H. Question: On Sheet C2.0 & Sheet C3.0 Detail 2 indicates that asphalt pavers are to be used at crosswalk ramps. ** Per UA Standards should this be truncated concrete pavers walk?

Answer: Yes, replace asphalt pavers in Detail 2, Sheet C3 with truncated dome concrete pavers as per UA Standards, coordinate color with owner.

I. Question: UL1 - Bega #8223P has been discontinued and is shown as a 120W-CF. Per NEW UA Campus Standards, this should be a Bega #7120 LED. Please confirm if the Bega #7120 LED fixture is to be bid in this project or provide alternate fixture.

Answer: Replace all Bega #8223P with Bega #7120 LED.

GENERAL

Acknowledge receipt of the Addendum in the space provided on page 00 41 43-2 of the Bid.

October 27, 2018

OLSSON

Consulting Engineers

302 E. Millsap Road

Fayetteville, Arkansas 72703

Phone (479)443-3404

Fax (479)443-4340